

P-1101/1102

PARAXYLENE TRUCK LOADING PUMP

TYPE: CENTRIFUGAL
CAPACITY: 90 m³/h
TDH: 30 MLC
INSTALLED POWER: 13.0 kW
MATERIAL: CS


APPROVED

By Ismail Sultan at 6:32 pm, Jan 11, 2017

LA-2102/2103

PARAXYLENE TRUCK LOADING ARM

SIZE: 4"
CAPACITY: 90 m³/h
MATERIAL: CS



- LEGEND:
- 1: DISPLACED VAPOUR FROM TRUCK LOADING TO BE VENTED TO SAFE LOCATION OUTSIDE TRUCK LOADING GANTRY
 - 2: VALVE CLOSES IN STAGES AT END OF LOADING
 - 3: LOCATION OF VENT PIPE WILL BE FIXED DURING ERECTION
 - 4: START/STOP AT TRUCK LOADING
 - 5: -
 - 6: PORTABLE DRIP PAN
 - 7: ALL INSULATED LINES TO BE PROVIDED WITH ELECTRICAL TRACING
 - 8: DELETED
 - 9: OVERFILLING PROTECTION
 - 10: PURGE CONNECTION: COUPLING 1 1/2" KAMLOK OPW, S.S. 633-FB ADAPTOR (NPT MALE) INCL. S.S. CAP (634-B)
 - 11: DRIP CATCHER + DRAIN PIPE FOR LOADING ARM

- LEGEND:
- F: OTHER SUPPLY
 - LO: LOCKED OPEN

10	17.09.12	ZMS	UAM	AS BUILT
09	15.12.03	MAA	IU	THIRD AS BUILT CORRECTED
08	10.7.2K	MIM	IU	SECOND AS BUILT CORRECTED
07	15.05.98	Wey	Go	FIRST AS BUILT CORRECTED
06	09.03.98	Wey	Go	AS BUILT
05	03.09.97	Zahr	Sch	TEMPORARY FILTER DELETED
04	24.04.97	Zahr	Sch	GENERAL REVISION
03	06.12.96	Zahr	Sch	VENDOR INFORMATION AND COMMENTS OF CLIENT ADDED
02	08.10.96	Zahr	Sch	GENERAL REVISION+DESIGN REVIEW 04.10.96
01	23.08.96	Mn		COMMENTS ACC. TO DESIGN REVIEW 13.08.96
rev.	date	made	checked	description of revision

checked	date	name	sign	scale	DIN size	sheet	sheet	project no	ident no	dok no	rev
	17.07.12	BIK		%	A1	05	05	2207-1387401-A017			

INTegrated LIQUID CHEMICAL TERMINAL & STORAGE FARM AT PORT QASIM / PAKISTAN	ENGRO	ENGRO PAKTANK TERMINAL LTD.	PID PARAXYLENE TRUCK LOADING	EPTL doc no	rev.	1	0	0	0	1	1
---	-------	-----------------------------	------------------------------	-------------	------	---	---	---	---	---	---